INGENIUS POLYPROPYLENE ENTRANCE MATTING


Heavy Duty Fibre Bonded Polypropylene Entrance Matting

SPECIFICATION

Use Recommendations

Entrance Matting for Shops, Office, Public Buildings, Hotels, Public Houses, Schools, Leisure Centres, Libraries, Post Offices, Universities, Theatres etc

Technical Details			
Manufacturing Process	ISO 2424	Needled pile floor covering	
Surface Aspect		Dilour	
Pile yarn composition		100% PP	
Backing	ISO 2424	Rubber Crumb	
Pile Weight		1120 g/m²	± 7.5%
Total Weight	ISO 8543	4070 g/m ²	± 7.5%
Pile Height		4.5 mm	± 0.5 mm
Total Height	ISO 1766	11.5 mm	± 0.5 mm



Thickness 10mm

Availability Rolls 15-20m x 2m wide

Cut lengths x 2m wide Special sizes up to 2m wide

Installation Ideally fully adhered to dry, sooth subfloors with approved adhesive, but can be looselaid, if

necessary, in matwells or as protective runners. Easily cut to size without fraying.

Lettered/Logo Mats We supply superb lettered and logo mats in Ingenius at remarkably inexpensive prices

(please ask for a copy of our current special price list

Aluminium Based Entrance Matting Ingenius can be incorporated into our Grime-Grabber, Alligator-Forefront and High Street Profile range of aluminium based matting for extra heavy traffic areas.

Maintenance We recommend daily vacuuming with suction attachment for best appearance retention

and longer wearing life. For periodic maintenance the best results can be achieved by the periodic use of a spray or dry extraction carpet cleaning machine or, where possible, by the

removal of the matting for pressure washing or steam cleaning.

The use of a mild detergent (neutral pH) cleaning solution in the carpet cleaning machine should loosen ingrained soiling and aid the removal of oils and grease. More stubborn stains should be treated a solvent based spot remover prior to re-cleaning with the detergent

solution.

Chewing Gum can be removed by freeze spraying or with a proprietary chewing gum remover and then scraped or combed out of the matting carpet pile. This should be done before the full cleaning process is started.

Jaymart